

PUBLIC NOTICE
Invitation for Sealed Bids on Timber Stumpage

Sealed bids will be accepted by the Oneida County Forestry Department at the Oneida County Courthouse, Second Floor, Room B206, Rhinelander, WI 54501 **UNTIL NOON ON MONDAY, NOVEMBER 2, 2020**. A timber sale prospectus and bid forms may be obtained by contacting the Forestry Office at the above address or by telephone at 715-369-6140. Bid packets can be viewed online at <http://www.co.oneida.wi.gov>

Oneida County Forest is third party certified. For information regarding certification, please contact the Forestry Office.

There are 21 tracts of timber for sale in the Towns of Cassian, Enterprise, Little Rice, Lynne and Woodboro comprising 1,624 acres. Total volume estimates are as follows:

Aspen	26,285 Tons / 11,602 Cds	White Pine	260 Tons / 126 Cds
Balsam Fir	3,070 Tons / 1,440 Cds	White Spruce	785 Tons / 340 Cds
Basswood	190 Tons / 100 Cds	Basswood Logs	55 MBF
Black Ash	1,900 Tons / 932 Cds	Black Ash Logs	76 MBF
Black Spruce	770 Tons / 378 Cds	Mixed Hwd Logs	213 MBF
Mixed Hwd	22,400 Tons / 9,402 Cds	Hard Maple Logs	13 MBF
Red Oak	275 Tons / 100 Cds	Red Maple Logs	5 MBF
Red Pine	9,355 Tons / 4,505 Cds	Red Oak Logs	55 MBF
Tamarack	645 Tons / 276 Cds		

The outside of the envelope must show the tract number and contractor name. Bids must include:

1. Tract number.
2. List of species to be cut and estimated volume.
3. Bid prices per Ton or MBF for each species and product.
4. Signature and address of each bidder.
5. A refundable bid bond in the form of check or cash must accompany each bid in the amount of 5% of the total bid value.

Successful bidders must provide proof of training to the State SFI standards at the time of contract signing. Minimum required deposit is 25% of successful bid value for each tract. The Forestry, Land & Recreation Committee reserves the right to reject any or all bids and/or select the bid most advantageous to Oneida County.

Bids will be publicly opened Monday, November 2, 2020 at 1:00 p.m. in Committee Room #1, 2nd Floor, Oneida County Court House, Rhinelander, WI. Successful bids will be awarded at the regularly scheduled Oneida County Forestry, Land & Recreation Committee meeting at 3:30 p.m. on Wednesday, November 4, 2020 in the County Board Room of the Oneida County Courthouse, 2nd floor, Rhinelander, WI. (Bid opening and awarding processes are subject to change without notice depending on the COVID-19 situation. Bid results will be posted online at www.co.oneida.wi.us/departments/fr/timber-sales/)

NOTICE FOR SEALED BIDS FOR STUMPAGE ON
ONEIDA COUNTY FOREST LANDS

BID DEADLINE: November 2, 2020 at NOON

Sealed bids will be received by the Oneida County Forestry Committee for the purchase of stumpage on the attached maps of Oneida County Forest Land, in accordance with the conditions set forth by the Committee. Additional information about the cutting areas is available from the Oneida County Forestry Office, PO Box 400, Rhinelander, WI 54501.

A REFUNDABLE BID BOND IN THE AMOUNT OF 5% OF THE TOTAL BID VALUE, IN THE FORM OF A CHECK OR CASH, MUST ACCOMPANY EACH BID.

If your bid is NOT SELECTED, the bid bond will be returned. If your bid is ACCEPTED, your bid bond will be held until the contract is signed on the terms below. If the contract is not signed within the required two (2) week period, your bid bond will be FORFEITED.

12.5 % will be added to the scale of all hand peeled wood. 16% will be added to the scale of all machine peeled wood.

SCALE PAYMENT WILL BE BY THE LOCK BOX HAUL PERMIT SYSTEM.

Irrevocable Letters of Credit and bonds will be considered on an individual basis in lieu of cash deposits.

Letters of Credit must have an expiration date one year past the contract end date.

Certificates of Insurance will be provided by the successful bidder at the signing of the contract, proving adequate liability with the limits of \$1,000,000 bodily injury and \$1,000,000 property damage and Worker's Compensation at statutory limits.

All successful bidders must provide proof of training to the State SFI standards at contract signing.

Successful bidders must sign contracts and pay balance of deposit within two weeks of receipt. Contract expiration dates vary from one to four years and may be renewed, with increased rates, at the discretion of the Committee. Total contract period shall be no more than 4 years from date issued. Upon signing of each contract, a deposit of 25% of the total successful bid value will be required. The minimum rates only apply to jobs sold by competitive bidding.



It is the bidder's responsibility to contact individual towns to determine if there are town ordinances relating to logging operations on town roads. Town contact information can be found on the Oneida County website (www.co.oneida.wi.gov) under "Municipalities" or by contacting the Oneida County Clerk at 715-369-6144.

PLEASE NOTE: Oneida County Forest Roads (Bowman Rd, Wickham Rd, Zimmer Rd, Shingle Mill Rd, Camp Six Rd, South Exit Rd, Bass Lake Rd, Cruisers Rd and Rozell Rd) *are not maintained in the winter by the County*. It is the responsibility of the Contractor to arrange snow plowing on these roads.

ALL BIDS MUST MEET MINIMUM BID PRICE PER SPECIES AS STATED ON SALE MAPS.

NOTE: Log specifications: Small end: 10” diameter inside the bark for hardwood and 9” diameter inside the bark for softwoods and capable of making a #3 Grade log. All logs to be scaled by the County prior to hauling.

NOTE: Bids will be publicly opened on Monday, November 2, 2020 at 1:00 p.m. in Committee Room #1, Second Floor, Oneida County Court House, Rhinelander, WI. Successful bidders will be announced Wednesday, November 4, 2020 at the regularly scheduled Forestry Committee meeting, scheduled to begin at 3:30 p.m. in the County Board Room, 2nd Floor, Oneida County Court House, Rhinelander, WI. (Bid opening and awarding process is subject to change without notice depending on the COVID-19 situation. Bid results will be posted online at <https://www.co.oneida.wi.us/departments/fr/timber-sales/>)

BID DEADLINE: **Monday, November 2, 2020 at NOON**; Oneida County Forestry Office; PO Box 400, Court House, 2nd Floor, Room B206, Rhinelander, WI 54501.

If you would like to be removed from our stumpage mailing list, complete the information below and return it to:

Oneida County Forestry Department
PO Box 400
Rhinelander WI 54501

NO, I do not wish to remain on the stumpage mailing list. Please remove my name.

NAME: _____

MAILING ADDRESS: _____

CITY / STATE / ZIP: _____

ONEIDA COUNTY FORESTRY DEPARTMENT
TIMBER SALE BID FORM

Send completed bids and bid bonds to: Oneida County Forestry, Land & Outdoor Recreation Committee, PO Box 400, Rhinelander, WI 54501

All sales are subject to the following conditions:

1. Only the tree species specified on the timber sale prospectus / map are to be cut. Utilization specifications designated for the sale area must be adhered to.
2. Contractor must comply with Slash Disposal Law, Sec.26.12(b), Wisconsin Statutes.
3. A Refundable Bid Bond must accompany each bid. Bid bond will be of 5% of the total bid value, in the form of a check or cash. A Performance Bond, in the form of cash, check, or letter of credit, equaling 25% of the total bid value is due upon signing of the contract.
4. No forest products shall be removed until scaled and marked by a representative of the Forestry Department and paid for unless otherwise specified in the contract scaling instructions. **NOTE: Log specifications: Small end: 10" diameter inside the bark for hardwood and 9" inside the bark for softwoods and capable of making a #3 grade log.**
5. All timber, marked or otherwise designated by the contract to be cut, shall be cut progressively and to the satisfaction of the representative of the Forestry Department, whether or not the quantity of such timber is more or less than the estimated comprising the operational specifications.
6. Undesignated trees cut or injured through carelessness and designated trees left through carelessness shall be paid for at double the stumpage rate. Timber wasted in tops and stumps shall be paid for at the stumpage rate.
7. Purchaser agrees to assume all liability for any damage or injury to persons or property, real or personal, resulting from Purchaser's operations under this contract and will hold Oneida County harmless from the same. The contractor shall furnish certification to the Oneida County Forestry Department that he / she is adequately insured with a reliable company so that Oneida County shall not be held liable in case of injury or death during and after the contract period. The limits of liability shall be \$1,000,000.00 bodily injury and \$1,000,000.00 property damage. The contractor shall also furnish proof of Workers Compensation Insurance at statutory limits. In the event the Purchaser's insurance is terminated for any reason, he / she shall immediately cease all activities otherwise permitted by the contract and provide written notice to the Forestry Department.
8. Roadways and trails will be kept free from brush, logs, pulp and waste material resulting from the operation. The Purchaser must abide by all rules regarding the use of roads, trails, and fire lanes. Additional constructed roads or trails must meet the approval of the Forestry Department.
9. Contractors will be required to furnish the Forestry Department with proof of SFI Logger Certification prior to signing contracts.

TURN OVER FOR SIDE 2

10. If, in the opinion of the Forestry Department, it is deemed that Contract provision are not being adhered to, all logging operations will be suspended. Operations may not be resumed without notification of the Forestry Department.
11. The Forestry Committee shall be the sole judge as to satisfactory compliance of contract conditions.
12. Timber sale contracts cannot be assigned in whole or in part without the consent of the Forestry Committee.
13. Any or all bids may be rejected by the Committee.
14. ALL BIDS PER SPECIES MUST MEET MINIMUM BID PRICE AS STATED ON PROSPECTUS.
15. Sample copies of County timber sale contracts are available for review at the Forestry Office in the Oneida County Court House.
16. All contracts will expire after the term indicated on the sale prospectus / map. One year extensions may be granted at the discretion of the Forestry, Land & Recreation Committee. Stumpage rates will be increased according to the following schedule:

One Year Contract:	1st Extension 5% rate increase 2nd Extension 10% rate increase 3rd Extension 15% rate increase
Two Year Contract:	1st Extension 10% rate increase 2nd Extension 15% rate increase
Three Year Contract:	1st Extension 15% rate increase (No additional extensions)

Total contract period, plus extensions, shall be no more than four years from date issued.

NOTE: The number of bids received per tract will not be revealed prior to bid deadline.

NOTE: Each tract that is bid on will be placed in a sealed envelope marked “Sealed Bid--Tract #__” and have the contractors name and address plainly printed on the front of the envelope.

BIDDER’S NAME AND ADDRESS MUST BE INCLUDED ON THE OUTSIDE OF THE ENVELOPE ALONG WITH THE TRACT NUMBER BEING BID.

I submit the following bid on TRACT # _____.

Utilization Specifications being Bid (**circle one**) 4" Top Whole Tree

Note: Make sure to use the volume estimates corresponding to the utilization specifications being bid. Bids must be per ton unless minimum bid is listed only by mbf or cords.

SPECIES	EST. VOLUME	BID/UNIT	SPECIES TOTAL
TOTAL BID			\$
Bid Deposit (5% of Bid Total) – Include with Bid:			\$
Performance Bond (25% of Bid Total) – Due at Contract Signing:			\$

I am aware that 12.5% will be added to the scale of hand-peeled pulpwood and 16% will be added to the scale of machine-peeled pulpwood. I am also aware the schedule of payment for all wood removed will be specified by the Committee on each individual contract.

Date: _____

Bidder's Name / Company (Please Print): _____

Mailing Address: _____

City, State, Zip Code: _____

Telephone Number: _____

Email Address: _____

Bidder's Signature: _____

Tract Number: _____

Conversion Rates used by Oneida County

<i>SPECIES</i>	<i>GREEN WEIGHT</i>		
	<u>lb/cd</u>	<u>Tons/cd</u>	<u>Tons/mbf</u>
Ash (Ab)	4600	2.30	5.06
Aspen (A)	4500	2.25	4.95
Balsam Fir (Fb)	4250	2.13	5.20
Basswood (Ba)	3850	1.93	4.25
Birch, White (Bw)	4800	2.40	5.28
Birch, Yellow (By)	5350	2.68	5.90
Cedar (C)	3150	1.58	3.86
Hemlock (H)	4800	2.40	5.86
Maple, Hard (sugar) (Mh)	5100	2.55	5.61
Maple, Red (Soft) (Mr)	4550	2.28	5.02
Mixed Hardwood (Mx)	4900	2.45	5.39
Oak, Red (Or)	5500	2.75	6.05
Pine, Jack (Pj)	4250	2.13	5.20
Pine, Red (Pr)	4500	2.25	5.49
Pine, White (Pw)	4200	2.10	5.13
Spruce (Sw, Sb)	4000	2.00	4.88
Tamarack (T)	4650	2.33	5.69

ONEIDA COUNTY FOREST-TIMBER SALE

McBear Pine

COMPARTMENT/ STAND, 71/1
 CUTTING AREA: 45 ACRES
 DESCRIPTION: T36N R4E, Sec. 1, E1/2 NW


TRACT # 4-20
 CONTRACT # _____
 TOWNSHIP OF Lynne
 CONTRACTOR: _____
 DATE SOLD: _____
 DATE COMPLETED: _____

CONTRACT LENGTH: 3 YEAR

EST. VOLUMES	MIN BID
4" TOP CORDWOOD by TON	
<u>RED PINE</u> (approx. 235 MBF, ~1815 cords)	3310 Tons \$ 19.30 / Ton
<u>WHITE PINE</u> (approx.. 40 MBF, ~110 Cords)	225 Tons \$ 8.40 / Ton
<u>MIXED HWD</u> (90% Red Maple, ~30 Cords)	75 Tons \$ 7.70 / Ton
<u>ASPEN</u> (~50 Cords)	115 Tons \$ 6.30 / Ton
<u>SPRUCE</u> (~20% Balsam Fir, ~60 Cords)	220 Tons \$ 6.30 / Ton

LEGEND

-  PINE HARVEST AREA
-  RPL RED PAINT LINE
-  SURVEY CORNER
-  LOGGING ROADS
-  NO CUT HWD AREAS
-  RESERVE SITES



NOTE:
 Heterobasidion root rot preventive spraying requirements will be implemented if Annosum is found within Oneida County or an adjacent county prior to or during the period of this contract. See Timber Sale Contract for details.

Scale: 4 inches = 1 mile

ADDITIONAL REGULATIONS

1. Harvest all merchantable pine, spruce, fir, mixed hardwoods and aspen. Do not cut or damage green marked pine. Our goal is to cut, run over or crush all nonmerchantable hardwood and balsam fir, 1" DBH saplings and larger, within the harvest area. Stump heights may not exceed 10". Stumps greater in height than 10" will be required to be recut by machine or hand cut. Stumps heights of less than 10" are desirable. Low cut stumps will minimize site prep and tree planting equipment damage.
2. Harvesting will be allowed year-round if the ground is dry or frozen to prevent rutting. All pine/spruce cut between May 1 and Sept 1 must be cut, skidded and hauled within 2 weeks. All winter cut pine must be hauled by May 1st of that harvest year.
3. This is a 70-year-old pine stand with an average DBH between 16" and 20". It's a very uniform 90+' tall stand of pine.
4. Damage to residual pine will not be tolerated. If residual damage occurs, additional harvesting restrictions will be imposed. Rutting will not be tolerated within these harvest areas. Utilization is 100" to a 4" top.
5. Two small areas of hardwood pole timber designated on the map with  cross hatching will not have the hardwood cut.
6. No decking or skidding on McCord Road or within the road ditches without written permission from Lynne Township. Any damage to Town road must be repaired to satisfaction of the Town. BMP's must be followed on all aspects of the sale.
7. Slash must be pulled back 10' from all logging roads. Sale slash height may not exceed 24" from the ground. Slash must be pulled behind the tree line along Mc Cord. Trees felled across the RPL must be pulled back into the sale area before limbing and bucking occurs.
8. Scattered dead standing trees must remain standing as wildlife snag trees unless they pose a logging safety hazard.
9. All logging roads and landings off Mc Cord Road must be leveled smooth upon sale completion and bermed or rocked closed. The sale performance bond will be held until all additional harvesting regulation requirements have been met.
10. No equipment or tree felling, including slash is to occur in the two green tree  marked reserve sites.
11. All items of Timber Sale contract also apply.

Est: Rhinelander DNR 4-2020

ONEIDA COUNTY FOREST-TIMBER SALE

Hwy Q PINE

COMPARTMENT/STAND, 10/4
 CUTTING AREA: **29 ACRES**
 DESCRIPTION: T35N R9E, Sec. 34, S1/2 SW, S1/2 SE,
 NENE

TRACT # 5-20
 CONTRACT # _____
 TOWNSHIP OF Enterprise
 CONTRACTOR: _____
 DATE SOLD: _____
 DATE COMPLETED: _____

CONTRACT LENGTH: 2 YEARS

Scale: 4 inches = 1 mile


EST. VOLUMES **MIN BID**

4" TOP CORDWOOD by TON

RED PINE 2925 tons \$ 26.30 / Ton
 (~1300 cords)

LEGEND

-  PINE HARVEST AREA
-  RED PAINT LINE
-  SURVEY CORNERS
-  NO EQUIPMENT AREA
-  LOGGING ROADS
-  BERM
-  L LANDING SITES
-  GO GAME OPENING



Langlade County

ADDITIONAL REGULATIONS

1. Harvesting will be allowed between July 15th and the following March 15th (spring break up) (oak wilt restrictions applied). Harvesting operations will be allowed as long as the ground is dry or frozen to prevent rutting. All pine cut between July 15 and Sept 1 must be cut, skidded and hauled within 2 weeks. All winter cut pine must be hauled by May 1st of that harvest year.
2. Harvest only unmarked red pine. Do not cut green marked red pine or any white pine. **Pine harvesting/felling will only occur with a fixed head processor or fixed head feller buncher with a 25' or more reach.** No "drive to the tree" feller bunchers or dangle head processors will be allowed to fell trees. Cut pine will be lifted and laid in the direction the buncher is going or where they came from. All cut pine will be laid in a ~20-25' wide "working area" where the skidder, processor, hand cutters and forwarder will operate. Our goal is to protect as much advanced red oak regeneration as possible. Long power pole skidding will be monitored and if damage to residual oak regeneration occurs, pole skidding will be stopped.
3. Damage to residual oak and hardwoods saplings will not be tolerated. If residual damage, outside the "working area" occurs, additional harvesting restrictions will be imposed. Rutting will not be tolerated within these harvest areas.
4. BMP's must be followed on all aspects of the sale. Utilization is 100" to a 4" top.
5. Crush, cut, uproot as much balsam fir as possible. No decking or skidding on Hwy Q or within its ditches.
6. Slash must be pulled back 10' from all logging roads and game openings. Sale slash height may not exceed 24" from the ground. All slash must be pulled behind the tree line along Hwy Q and less than 24" in height. Stump heights may not exceed 10". Trees felled across the RPL must be pulled back into the sale area before limbing and bucking occurs.
7. All logging roads off Hwy Q must be leveled smooth upon sale completion. Game openings (GO) if used for landing sites must be returned to their original condition or better with no debris piles around the GO and dozed off soil will be returned to the GO and leveled and seeded at contractors' expense. Seed source, mixtures and amounts must have County approval. The logging road access along the east side of the sale must be bermed/rocked at end of sale. The sale performance bond will be held until this all occurs.
8. Scattered dead standing trees must remain standing as wildlife snag trees unless they pose a logging safety hazard.

ONEIDA COUNTY FOREST-TIMBER SALE

Porky Oak


CMPT / STAND: 45 / 9
 SALE AREA: 22 ACRES, HARVEST AREA 19 ACRES
 DESCRIPTION: T37N R7E, Sec. 13, NBSW, NWSE

TRACT # 8-20
 CONTRACT # _____
 TOWNSHIP OF Cassian
 CONTRACTOR: _____
 DATE SOLD: _____
 DATE COMPLETED: _____

CONTRACT LENGTH: 3 YEARS
 Scale: 4 inches = 1 mile

EST. VOLUMES	MIN BID
RED OAK 275 tons (~100 cords)	\$ 5.00 / TON
RED OAK 42 MBF	\$150.00 / MBF

SCALE: 1" = 1/4 MILE



LEGEND

	HARVEST AREA
	BERM
	BPL BLUE PAINT LINE (Private Property Line)
	PVT PRIVATE PROPERTY
	PRIVATE DRIVEWAY
	LOGGING ROADS
	K KEG
	CENTER OF SECTION

Additional Regulations



- In the harvest area, harvest all orange marked red oak, approximately 201 trees. Logging operations are allowed from July 15th to the following March 15th (oak wilt restrictions) as long as the ground is sufficiently dry or frozen to prevent rutting. NO operations allowed from spring break up to the following July 15th. Time restrictions will be imposed if excessive rutting occurs in the woods or roads or if excessive damage to the residual trees and regeneration occur.
- This sale must be cut and skidded contiguously and concurrently. Utilization is 100" stick to a 4" top. A majority of the approximate 201 marked red oak are 18" to 22" in diameter. Pole length skidding is permitted only if residual damage to trees and regeneration does not occur. Standing dead, nest or cavity trees are not to be cut unless they pose a safety hazard. Large intact red oak tree tops are desirable to protect oak regeneration, a natural fence to deer browsing.
- No new roads will be permitted. Existing roads may be opened and improved, and landing sites may be constructed with prior approval of the County. All roads and landings must be graded flat at the end of each harvest season and at the end of the sale and returned to as good or better condition. No stumps or soil are to be pushed into or within 25' of any wetland, water body or vernal pond. All access roads are to be blocked with rocks, or multiple large stumps or bermed at the end of each harvest season and at the end of the sale. Bond money will not be returned until all berms, roads and landing work is completed and approved by the County Forest.
- No decking of forest products or equipment operation on or within the ditches of Ole Lake Road without written permission of Cassian Township. No equipment may be operated within 15' of any wetland unless the ground is frozen. No harvesting slash may be left in any vernal ponds or wetlands scattered throughout the sale area. BMP's must be followed on all aspects of the sale.
- A minimum of 5 days' notice must be given to the County Forestry Office before any logging operations can proceed (road/landing site building, cutting, skidding, hauling).
- The Private Driveway may not be used for any harvesting activities. If damage does occur to this Private Driveway due to harvesting activities, the harvesting contractor is responsible for all repairs (grading, ditching, leveling and gravelling if necessary). Whatever is necessary to restore this Driveway to its original condition.
- All terms of the County Timber Sale Contract also apply.

Est: Rhinelander DNR & County Forestry Dept 2-2020

Compartment / Stand 58/7, 65/6 & 18
 Harvest Area 75 Ac (51 ac Aspen, 24
 ac Pine)
 34 Ac Reserve Areas
 Legal Desc. T36N R5E
 Sec. 4: SWSE, SW1/4, SWNW
 Sec. 5: SENE

Oneida County Forest Gobbler Pine

Tract # 10-20
 Town of Little Rice
 Contract No.: _____
 Contractor: _____
 Date Sold: _____
 Date Completed: _____
 Contract Length: 3 Years



NOTE: Heterobasidion (Annosum) Root Rot preventative spraying requirements will be implemented if Heterobasidion (Annosum) Root Rot is found in Oneida County or an adjacent county prior to or during the period of this contract. See Timber Sale Contract for details.

*Pine = 92% Red, 5% White and 3% Fir
 **Mx Hwd = 76% W Birch, 20% R Maple and 4% H Maple

4" Top	Est. Volume	Min. Bid
*Pine	1455 Tons (650 cd)	\$17.50/Ton
Aspen	700 Tons (310 cd)	\$8.40/Ton
**MX Hwd	880 Tons (370 cd)	\$8.40/Ton

Legend

- Pine Area
- Aspen Area
- Reserve Areas
- Survey Corner
- Keg/Swamp
- RPL - Red Paint Line
- BPL - Blue Paint Line
- YPL - Yellow Paint Line

Additional Regulations:

- In the Aspen Harvest Areas cut all Aspen, White Birch and Fir 1" diameter or larger and only Pine marked with orange paint leaving orange visible on the stump. Do not cut any other species.
 In the Pine areas harvest only those trees marked with orange paint, leaving orange visible on the stumps.
 Utilization on all species is a 100" stick to a 4" top. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard.
 No harvesting or skidding in the reserve areas.
- Dry or frozen ground conditions will be required for harvesting and hauling activities. Year round operations will be permitted as long as rutting or road damage does not occur. Time restrictions may be imposed if excessive rutting occurs in the woods or on the roads or if excessive damage to the residual trees occurs. No whole tree skidding. Maximum pole length is 17' for non-utility pole material. If utility poles are to be harvested, all non-utility pole material shall be harvested first to allow removal of utility poles without damaging the residual stand.
 No pine may be decked on site for more than 2 weeks between May 1 and Sept. 1. Pine harvested during winter months must be hauled from the site by May 1.
- Any new roads and all landing sites must have prior approval of the County. All logging roads and landings must be leveled and bermed/rocked off at the end of each harvest season and at the end of the sale. Bond money will not be returned until all road/landing rehabilitation is complete.
- Decking or skidding on Town Roads will only be done with permission of the Town of Little Rice and only when the road is dry or frozen to prevent damage. Any damage to the roads will be immediately repaired to the satisfaction of the town (including grading and graveling if required). Wood decked along the road must be kept far enough off the road so as not to pose a danger to traffic. No felling of trees across the town roads.
- No equipment or slash is allowed in the wetland areas within or adjacent to the sale. Equipment may not be operated within 15 feet of any wetland unless ground is dry or frozen.
- Slash must be pulled back a minimum of 25 ft from the edge of the Town Roads and must be cut to no higher than 2 ft throughout the sale.
- Gobbler Lk Road is an ATV and Snowmobile trail. Caution signs must be placed at both ends of the sale while logging is active and when hauling.
- All items listed in the Oneida County Timber Sale Contract apply. All applicable BMP's will be followed. Sale Est. JL 5/20


Oneida County Forest

Rozell Aspen

Compartment / Stand 53/9, 11, 12
 Harvest Area 63 Ac + 18 Ac GTR
 Legal Description- T36N R5E
 Sec. 27 NE1/4, NWSE



Tract # 11-20
 Town of Little Rice
 Contract No.: _____
 Contractor: _____
 Date Sold: _____
 Date Completed: _____
 Contract Length: 3 years



4" Top	Est. Volume	Min. Bid
Aspen	1085 Tons (485 cd)	\$6.10/Ton
*MX Hardwood	2160 Tons (940 cd)	\$5.50/Ton
Balsam	310 Tons (145 cd)	\$3.20/Ton
Black Spruce	170 Tons (80cd)	\$4.60/Ton
Tamarack	110 Tons (45cd)	\$1.80/Ton

Whole Tree	Est. Volume	Min. Bid
Aspen	1525 Tons (704 cd)	\$4.34/Ton
*MX Hardwood	3050 Tons (1325 cd)	\$3.90/Ton
Balsam	530 Tons (250 cd)	\$1.87/Ton
Black Spruce	255 Tons (120 cd)	\$3.07/Ton
Tamarack	145 Tons (65 cd)	\$1.37/Ton

*MX Hardwood Pulp contains approximately 82% Red Maple, 17% White Birch, 1% Hard Maple

Legend	
	Coppice Harvest Area
	BI Spr/Tam Area
	State Land
	Grass/Brush
	Tag Alder
	Private Land
	Red Paint Line
	Blue Paint Line
	Town Road
	Trail
	Section Corner
	GTR Area

Additional Regulations:

- Coppice Harvest Area**- cut all aspen, balsam fir, white birch, red maple, hard maple, and ironwood 1" diameter or larger. Do not cut cedar, tamarack, white spruce, yellow birch, oak, pine, or trees marked with green paint.
- BI Spruce/Tam Harvest Area**- cut all black spruce, tamarack, aspen, balsam fir, white birch, red maple, and hard maple. Do not cut cedar, white spruce, yellow birch, oak, pine or trees marked with green paint.
- Utilization on all species is a 100" stick to a 4" top or whole tree. If harvesting whole tree, every 10th tree top above the 4" diameter must be left evenly scattered in the harvest area. Any den or nest trees should be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard.
- Harvest Requirements**- Dry or frozen conditions will be required for harvesting, skidding or hauling activities. Harvesting will be permitted year round and only if rutting and road damage does not occur. Additional restrictions will be imposed if excessive rutting occurs in the woods or on roads or if excessive damage to the residual trees occurs. Tree length skidding is permitted only if residual damage does not occur. Damage to listed residual (cedar, tamarack, white spruce, yellow birch, oak, pine, or trees marked with green paint) will not be permitted. Stump Heights may not exceed 10 inches from the ground.
- Grass openings may be used for landings, but must be completely restored and free of debris. Any soil removed from grass openings must be spread level across the opening to facilitate reseeding and future mowings.
- No new roads will be permitted. Existing trails may be opened/improved and landing sites may be constructed with prior approval of the County. Rozell Rd. is a designated ATV trail. This road must be kept open at all times and remain in a safe useable condition. During non winter operations (harvesting, skidding or trucking) cautionary signs must be placed at both ends of Rozell Rd where trucking will occur. During the snowmobile season, Kelly Fire Ln. is a designated snowmobile trail. The snowmobile trail must remain snow covered with cautionary signs placed on Kelly Fire Ln. All roads/trails must be returned to their original condition or better at the end of sale and must be blocked with rocks/berm at Rozell Rd. Bond money will not be returned until all road/landing/trail rehabilitation is complete.
- No equipment or slash is allowed in the wetland areas, within or adjacent to the sale. All trees felled across the blue lines must be pulled back into the sale before limbing. Equipment may not be operated within 15 feet of any wetland unless ground is dry or frozen.
- All items listed in the Oneida County Timber Sale Contract apply. All applicable BMP's will be followed. Sale Est. MO/JP 1/2020


Oneida County Forest

5 Point Aspen

Compartment / Stand 103/2, 15
 Harvest Area: 73 Ac Total Harvest 6 Ac Reserve
 (68 ac Aspen, 5 ac. Marked Hwd)
 Legal Desc. T37N R4E
 Sec. 17 W1/2 SW Sec. 18 E1/2 SE
 Sec. 19 NE NE Sec. 20 NW NW



Tract # 13-20
 Town of Lynne
 Contract No.: _____
 Contractor: _____
 Date Sold: _____
 Date Completed: _____
 Contract Length: 3 years



4" Top	Est. Volume	Min. Bid
Aspen	3110 Tons (1380 cd)	\$6.70/Ton
*MX Hardwood	1040 Tons (425 cd)	\$6.10/Ton
Balsam	265 Tons (125 cd)	\$3.70/Ton
W Spruce	360 Tons (180 Cd)	\$6.70/Ton

Whole Tree	Est. Volume	Min. Bid
Aspen	4265 Tons (1895 cd)	\$4.89/Ton
*MX Hardwood	1520 Tons (620 cd)	\$4.17/Ton
Balsam	545 Tons (260 cd)	\$1.80/Ton
W Spruce	475 Tons (240 Cd)	\$5.08/Ton

*MX Hardwood Pulp contains approximately 70% R Maple, 20% H Maple, 6% Ash, 3% Basswood, 1% Misc. Mixed hardwood pulp also includes approx. 1000 bf of Basswood and Ash logs.

Legend

Aspen Area	RPL	Red Paint Line
Marked Hardwood Area	YPL	Yellow Paint Line
Retention Area	BPL	Blue Paint Line
Tag Alder/Cedar	+	Survey Corner
Town Road		Power Line

Additional Regulations:

- In the Aspen Area cut all Aspen, Maple, White Birch, Ash, Elm, Ironwood and Balsam Fir. Only cut spruce between 10" and 18" dbh. Do not cut any other species or W Spruce smaller than 10" and larger than 18".
 In the Marked Hardwood Area harvest all Aspen, Balsam Fir, Ironwood and all trees marked with orange paint, leaving orange visible on the stump. Utilization on all species is a 100" stick to a 4" top or whole tree. If harvesting whole tree, every 10th tree top above the 4" diameter must be left evenly scattered in the harvest area. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard.
- Dry or frozen ground conditions will be required for harvesting and hauling activities. Access trails have numerous wet areas and the presence of numerous tag alder draws within the sale will likely require frozen ground. Year round operations may be permitted as long as rutting or road damage does not occur. Time restrictions may be imposed if excessive rutting occurs in the woods or on the roads or if excessive damage to the residual trees occurs.
- Any new roads must have approval of the County prior to construction. Existing roads may be opened and improved and landing sites may be constructed with prior approval of the County. All trails and the powerline Right of Way must be returned to their original condition or better at the end of sale and must be closed with rocks, berms or gates at the end of each harvest season and at the end of the sale. Bond money will not be returned until all road/landing rehabilitation is complete.
- No equipment is allowed in the wetland areas within or adjacent to the sale unless the ground is frozen. No slash is to be left in any wetlands within or adjacent to the sale. Equipment may not be operated within 15 feet of any wetland unless ground is dry or frozen. No equipment is allowed across the Blue Paint Line. Any trees felled across the Blue Paint Line must be pulled back onto County property before limbing. No slash is to be left on private property. Witness trees near the Survey Corner have been painted blue. Do not cut the blue painted trees or disturb the survey corner.
- Slash must be pulled back a minimum of 25 ft from the edge of the town road. Decking or skidding on N. Turcott Rd is prohibited unless permission is obtained from the Town of Lynne. The road must be repaired to the satisfaction of the Town, if it is used for skidding or decking.
- All items listed in the Oneida County Timber Sale Contract apply. All applicable BMP's will be followed. Sale Est. PF/BB 4/20


ONEIDA COUNTY FOREST-TIMBER SALE

RICE RIVER ASPEN

CMPT / STAND: 53 / 2, 4
 SALE AREA: 142 acres, CUTTING AREA: 123 acres
 DESCRIPTION: T36N R5E, Sec. 22 W1/2
 T36N R5E, Sec. 27, N1/2NW
 CONTRACT LENGTH: 4 YEARS
 Scale: 4 inches = 1 mile

TRACT # 12-20
 CONTRACT # _____
 TOWNSHIP OF Little Rice
 CONTRACTOR: _____
 DATE SOLD: _____
 DATE COMPLETED: _____

EST. VOLUMES		MIN BID	OR	EST. VOLUMES		MIN BID
4" TOP CORDWOOD by TON				**WHOLE TREE by TON**		
ASPEN	3745 tons (1595 cds)	\$ 8.40 / TON		ASPEN	4225 Tons	\$ 7.45 / TON
MX HRD	1600 tons (695 cds)	\$ 8.40 / TON	(Mixed Hrds ~80%, 15% white birch, 5% ash)	MX HRD	2265 Tons	\$ 5.93 / TON
BALSAM FIR	655 tons (305 cds)	\$ 3.90 / TON		BALSAM FIR	1300 Tons	\$ 1.97 / TON
BLK SPRUCE	395 tons (15% white spruce) (195 cds)	\$ 7.00 / TON		BLACK SPRUCE	605 Tons (15% white spruce)	\$ 4.57 / TON



- LEGEND**
-  HARVEST AREA
 -  LOGGING ROADS
 -  BERM/ROCKS
 -  SG/A SWAMP GRASS/ALDER
 -  R P L RED PAINT LINE
 -  RETENTION AREAS
 -  WET ALDER DRAWS
 -  G GAME OPENING
 -  SECTION CORNER

ONEIDA COUNTY FOREST-TIMBER SALE

RICE RIVER ASPEN

CMPT / STAND: 53 / 2, 4
SALE AREA: 142 acres, CUTTING AREA: 123 acres
DESCRIPTION: T36N R5E, Sec. 22 W1/2
T36N R5E, Sec. 27, N1/2NW
CONTRACT LENGTH: 4 YEARS
Scale: 4 inches = 1 mile

TRACT # 12-20
CONTRACT # _____
TOWNSHIP OF Little Rice
CONTRACTOR: _____
DATE SOLD: _____
DATE COMPLETED: _____

ADDITIONAL REGULATIONS

1. **Harvest all;** Aspen, Maple, White Birch, Ash, Balsam Fir, Black Spruce, as well as all White Spruce greater than 8" up to 16" DBH. The smaller and larger diameter White Spruce will be retained for wildlife. Do not cut any other species. Cut all 1' to 5" maple and balsam fir. Logging operations are allowed year-round as long as the ground is sufficiently dry or frozen to prevent rutting. Harvesting operations will most likely need to occur during the winter months due to wetter, soil conditions and wetland crossings to the islands. The sale is mostly flat with an old road system throughout.
2. Utilization is 100" stick to a 4" top or as bid. If harvesting whole tree, 1 in 10 tops above the standard 4" top must be left on site and evenly scattered throughout the sale.
3. All Roads and landings must have permission of the County prior to construction and must be graded flat and bermed off or rocked off at the end of the sale. The grass opening may be used as a landing. Following the harvest this grass opening must be free of debris and graded flat leaving it mowable. Topsoil will not be removed from the opening and pushed to the edges with the harvesting debris. Bond money will not be returned until all road and landing work is completed.
4. No decking of forest products or equipment operation on or within the ditches of Rozell Road without permission of the County. The Kelly Fire Lane is a snowmobile trail. It must be kept open, free of equipment, snow covered during the snowmobile season, and in a safe usable condition at all times. Harvesting/Logging ahead cautionary signs must be placed east and west of this timber sale along the Rozell Road while cutting, skidding and hauling occurs.
5. No equipment may be operated within 15' of any wetland unless the ground is frozen.
6. Slash must be pulled back 10' behind the tree line along the edge of Rozell Road and must be cut to 24" or less in height within 25' of Rozell Road.
7. BMP's must be followed on all aspects of the sale.
8. All dead standing trees and cavity trees must be left standing unless they pose a safety hazard to the harvesting operation.
9. All terms of the County Timber Sale Contract also apply.


Oneida County Forest

Pork-E-Pine

Compartment / Stand 51/3, 52,1
 Harvest Area: 16 Acres
 Legal Desc. T37N R7E
 Sec. 15 SESW
 Sec. 22 NENW, NWNE



Tract # 14-20
 Town of Cassian
 Contract No.: _____
 Contractor: _____
 Date Sold: _____
 Date Completed: _____
 Contract Length: 3 years



4" Top	Est. Volume	Min. Bid
Red Pine	545 Tons (240 cords)	\$17.50/Ton
Aspen	110 Tons (50 cords)	\$8.40/Ton

Note: Heterobasidial (Annosum) Root Disease preventative spraying requirements will be implemented if HRD is found in Oneida County or an adjacent county prior to or during the period of this contract. See Timber Sale Contract for details.

Legend

	Harvest Area		Old Town Dump
	Town Road		Snowmobile Trail
	Survey Marker	R.P.L.	Red Paint Line

* Year round harvesting may occur as long as the site is dry or frozen to prevent rutting


Additional Regulations:

- In the Harvest Area cut all aspen and orange marked trees leaving orange visible on the stump. In first thinning stand, cut rows are designated with two orange dots, cut all trees within these rows (Cut 1 row, leave 2 rows). Utilization on all species is a 100" stick to a 4" top. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard.
- No new roads will be permitted. Existing roads may be opened and improved and landing sites may be constructed with prior approval of the County. No equipment will be allowed to operate on the area of the old town dump site. If snowmobile trail is used during snowmobile season cautionary signs must be placed along the trail. The trail surface must remain snow covered and all debris must be cleared from the trail surface daily.
- Slash must be pulled back a minimum of 10 ft from the edge of town roads and snowmobile trails and must be cut to no higher than 2 ft off the ground within 50 ft of the town roads.
- No slash or equipment allowed in wetland areas adjacent to the sale. Equipment may not operate within 15 feet of any wetland unless ground is dry or frozen.
- Decking on Timber Lake Road or Spruce Lake Road will only be allowed with permission of the Town of Cassian. Any damage to the roads will be immediately repaired to the satisfaction of the town. Wood decked along the road / snowmobile trail must be kept far enough off the road / trail so as not to pose a danger to traffic.
- No pine may be decked on site for more than 2 weeks between May 1 and Sept 1. Wood cut and decked during winter must be hauled off of the County Forest by May 1st.
- All items listed in the Oneida County Timber Sale Contract apply. All applicable BMP's will be followed.

Sale Est. JT 4/20


Oneida County Forest Goodyear Aspen

Compartment / Stand 43/6,7
Harvest area: 42 total acres (40 Cut acres, 2 Ac Reserve/GTR)
Legal Desc. T37N R7E
Sec. 36 NW1/4



Approximate Sale Location

Tract # 15-20
Town of Cassian
Contract No.: _____
Contractor: _____
Date Sold: _____
Date Completed: _____
Contract Length: 3 years



4" Top	Est. Volume	Min. Bid
Aspen	1715 Tons (760 cd)	\$8.40/Ton
*MX Hardwood	205 Tons (90 cd)	\$8.40/Ton
Balsam	335 Tons (160 cd)	\$7.00/Ton

Whole Tree	Est. Volume	Min. Bid
Aspen	2315 Tons (1030 cd)	\$6.23/Ton
*MX Hardwood	290 Tons (125 cd)	\$5.94/Ton
Balsam	510 Tons (245 cd)	\$4.60/Ton

*MX Hardwood Pulp contains approximately 41% R Maple, 58% White Birch, 1% Misc
*Balsam contains approximately 3% White Spruce

Legend	
	Clearcut Area
	RPL Red Paint Line
	BPL Blue Paint Line
	Retention Area
	Survey Corner
	Town Road
	Ski Trail
	Gate
	Snowmobile Trail
	Waterbodies

Additional Regulations:

- In the Harvest Area cut all aspen, red maple, white birch, and balsam fir. Only cut white spruce greater than 8" and less than 18". Do not cut any red pine, cherry, white pine or red oak in the sale boundary. Utilization on all species is a 100" stick to a 4" top or whole tree. If harvesting whole tree, every 10th tree top above the 4" diameter must be left evenly scattered in the harvest area. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard. No trees are to be cut across the blue line and any trees that are felled across the blue line must be pulled back into the sale boundary. Harvesting is limited to non-ski season. (Post spring break-up to Nov 15th.)
- Dry will be required for harvesting and hauling activities. Operations after spring breakup through November 15th may be permitted as long as rutting or road damage does not occur. Time restrictions may be imposed if excessive rutting occurs in the woods or on the roads or if excessive damage to the residual trees occurs.
- A new logging road may be created on the north side of the western sale area, south of Goodyear Lake Road. Existing roads may be opened and improved and landing sites may be constructed with prior approval of the County. One stub road/landing may be permitted on the North end of the western piece. The main access trail is a cross country ski trail. Gates must be closed when no one is on site if working during non-ski season. All trails will be returned to their original condition or better at the end of each harvest season and at the end of the sale. Bond money will not be returned until all road/landing rehabilitation is complete.
- Decking on Goodyear Lake Road will only be allowed with the permission of Town of Cassian. Any damage will be immediately repaired to the satisfaction of the Town. Wood decking off the road must be kept far enough off the road so as not to pose a danger to traffic.
- No equipment or slash is allowed in the wetland areas within or adjacent to the sale. Equipment may not be operated within 15 feet of any wetland.
- Slash must be pulled back a minimum of 25 ft from the edge of the cross country ski trail and the town road and must be cut to no higher than 2 ft off the ground within 50 ft of the trail. Logging signs will be required while harvesting on the town road and the ski trail.
- All items listed in the Oneida County Timber Sale Contract apply. All applicable BMP's will be followed. Sale Est. BB/PF 7/20

Compartment/Stand: 25/ 1 & 12

ONEIDA COUNTY FOREST


Tract #17-20

Harvest Area: 32 Acres (31 Harvest acres, 1 acre Retention)

Pandemic Pine

Town of Enterprise

Legal Desc; T35N R9E Sec. 19 SENE, NESE



Approximate Sale Location

Contract No. _____


Contractor: _____

Date Sold: _____

Date Completed: _____

Contract Length: 2 Years

Legend		Town Rd	R P L	Red Paint Line	
	Harvest Area		Woods Rd		Fence Line
	Retention Area		Survey Corner		Riparian Zone
					Waterbodies



	<u>Est. Volume</u>	<u>Min. Bid</u>
<u>4" Top</u>		
Red Pine	1120 Tons (500 cd)	\$17.50/Ton
Balsam Fir	65 Tons (30cd) (*includes 25% White Spruce)	\$4.40/Ton
<u>Whole Tree</u>		
Red Pine	1500 Tons (665 cd)	\$13.07/Ton
Balsam Fir	160 Tons (75 cd) (includes 20% White Spruce)	\$1.79/Ton

NOTE:
Heterobasidion root rot preventive spraying requirements will be implemented if Annosum is found within Oneida County or an adjacent county prior to or during the period of this contract. See Timber Sale Contract for details.


Additional Regulations

- In the Pine Area, harvest all orange marked pine, leaving orange paint on the stumps. Harvest all (1"+) Balsam Fir & (6"+) white spruce. Do not harvest any other trees. Standing dead trees are to remain standing unless they pose a hazard. Logging is permitted year round as long as the ground is dry enough or frozen to prevent rutting. If rutting occurs, frozen ground only restrictions will be applied. No damage to the residual trees will be tolerated.
- All pine cut between May 1 and September 1 must be skidded and hauled within 2 weeks. All winter cut pine must be hauled by May 1st of the year. No whole tree skidding of Pine. Maximum pole length is 19'. Utility poles will be dealt with on a tree by tree basis.
- Utilization is 100" stick to a 4" top or as bid. All standing dead trees will remain standing unless they pose a safety hazard. Dead and down trees are not to be crushed by equipment, if downed woody debris is in the way, move the wood aside.
- If harvesting whole tree, every 10th tree top above the standard 4" diameter must be left in the woods where the tree was felled.
- Absolutely no skidding on John's Memorial Drive or Camp 6 Road or within their ditch lines. It is okay to skid if the roads are frozen. Any new roads or landings must have approval of the County prior to construction. If decking occurs along the road, skidders shall unload from the woods side. All roads and landings must be leveled and cleared of debris upon completion of sale. Bond money will not be returned until road/landing rehab is complete.
- No equipment, skidding, decking or slash is permitted in the lowland areas within or adjacent to the sale or within the reserve/riparian zone. All slash must be pulled back 10' from all roads and cut to no higher than 2' off the ground. Stump height may not exceed 10".
- BMP's must be followed on all aspects of the sale. All County Forest Roads and logging roads must be in as good & better condition once the timber sale is done.
- The remnants of a homestead lie in the western part of the north pine area. These features have been flagged prior to harvesting and must be avoided. No skidding on or over these features and felling of trees on them must be avoided.
- Logging signs will be needed for Camp Six Road and John's Memorial Drive.
- All terms of the Timber Sale Contract also apply.

Oneida County Forest Lamer's Aspen

Tract # 19-20
 Town of Lynne
 Contract No.: _____
 Contractor: _____
 Date Sold: _____
 Date Completed: _____
 Contract Length: 3 years

Compartment / Stand 108/3
 Harvest Area 64 acres + 10 Ac Reserve (74 Ac Total)
 Legal Desc. T37N R4E Sec. 22 SENE, NESE
 Sec. 23: N1/2SW, S1/2NW



4" Top	Est. Volume	Min. Bid
Aspen	2150 Tons (955 cd)	\$7.60/Ton
*MX Hardwood	370 Tons (150 cd)	\$7.60/Ton
Balsam Fir	185 Tons (85 cd)	\$4.20/Ton
W Pine	35 Tons (16 cd)	\$10.50/Ton
*MX Hardwood contains 61% W Birch and 39% R Maple/Misc		
Whole Tree	Est. Volume	Min. Bid
Aspen	2885 Tons (1280 cd)	\$5.66/Ton
*MX Hardwood	540 Tons (220 cd)	\$5.20/Ton
Balsam Fir	275 Tons (130 cd)	\$2.82/Ton
W Pine	50 Tons (23 cd)	\$7.35/Ton
*MX Hardwood contains 61% W Birch and 39% R Maple/Misc		

Legend

- Harvest Area
- Reserve Area
- Red Paint Line
- Blue Paint Line
- Town Road
- Gate
- Snowmobile/ATV Trail
- Survey Corner
- Logging Road / Skid Trail
- Keg/Wetland
- Grass Opening


Additional Regulations

1. Harvest all Aspen, Maple, Balsam Fir and White Birch 1" diameter or larger, and only those pine marked with orange paint, leaving orange on the stump. Do not cut any aspen within 50 ft of the grass openings. Year round harvesting is permitted as long as the ground is dry or frozen to prevent rutting and damage to residual trees does not occur. Frozen ground only restrictions will be applied if rutting or damage to residual occurs.
2. Utilization is 100" stick to a 4" top or whole tree. If harvesting whole tree, every 10th top above the standard 4" top shall be left evenly scattered throughout the sale area.
3. Slash is to be pulled back from the town roads a minimum of 25 ft and cut to no higher than 2 ft from the ground within that zone. Slash control outside the 25 ft zone is not required. Skidding or decking on the town roads is prohibited unless permission is granted by the Town. All damage to the road must be repaired immediately to the satisfaction of the Town. Decks must be far enough off the road to prevent any safety issues.
4. No new roads permitted. Existing roads may be improved and landings and turn-arounds constructed with prior approval of the County. All roads must be leveled, and if they were blocked off prior to the sale they must be blocked with rocks, a berm or gate at the end of each harvesting season and at the end of the sale. The grass openings may be used for landings and must be completely clear of slash and leveled to facilitate mowing at the end of each harvest season and at the end of the sale. If topsoil is removed from the grass openings, it must all be spread back over and smoothed out on the areas from which it was removed. Part of Lamer Springs Rd is a snowmobile/ATV trail. Cautionary signs must be posted on both ends of the sale any time hauling or skidding on the road is active.
5. No equipment is allowed to operate within 15 ft of any wetland or vernal pond within or adjacent to the sale unless the ground is dry or frozen. No slash is to be left in any wetland or vernal pond. No equipment or slash is allowed within the reserve areas. All trees must be pulled back across blue paint line onto sale area prior to limbing. No slash is to be left across the blue lines.
6. All dead standing trees or den/nest trees must be left standing unless they pose a safety hazard to the harvesting operations.
7. All items listed in the Oneida County Timber Sale Contract apply. All applicable BMP's will be enforced. Sale Est. JB 7/20. Writeup by PF 9/20

Oneida County Forest


Epidemic Aspen

Compartment / Stand 29/2,8 & 30/22
 118 Total acres, 105 Harvest acres, 13 Retention acres
 Legal Desc. T36N R7E
 Sec. 1 W1/2 NW1/4, NW1/4 SW1/4
 Sec. 2 NE 1/4, E1/2 NW1/4, NE1/4 SE1/4



Approximate Sale Location

Tract # 21-20
 Town of Woodboro
 Contract No.: _____
 Contractor: _____
 Date Sold: _____
 Date Completed: _____
 Contract Length: 4 years



4" Top	Est. Volume	Min. Bid
Aspen	5765 Tons (2565 cd)	\$8.40/Ton
*MX Hardwood	1300 Tons (580 cd)	\$8.40/Ton

Whole Tree	Est. Volume	Min. Bid
Aspen	7880 Tons (3505 cd)	\$6.14/Ton
*MX Hardwood	2170 Tons (940 cd)	\$5.03/Ton

*MX Hardwood Pulp contains approximately 77% R Maple, 14% White Birch, 6% red oak 3% basswood
 **Sale contains several truck loads of red oak logs.

Legend	
	Harvest Area
	RPL Red Paint Line
	Retention Area
	PPL Purple Paint line
	Town Road
	Survey Corner
	Snowmobile Trail
	Gate
	Waterbodies
	Ski/Bike Trail
	Single Track Trails


Additional Regulations:

- In the Harvest Area cut all aspen, maples, cherry, white birch, white ash, basswood, ironwood, and orange marked oak. Do not cut any other species, unmarked red oak and balsam fir. Utilization on all species is a 100" stick to a 4" top or whole tree. If harvesting whole tree, every 10th tree top above the 4" diameter must be left evenly scattered in the harvest area. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard. No trees are to be cut across the sale boundary and any trees that are felled across the boundary must be pulled back into the sale.
- Block A's harvesting is allowed Jul15th -spring break up due to oak wilt. Harvesting is allowed from to July 15th-November 15th for blocks B through E, due to oak wilt restrictions and ski trail concerns and as long as rutting or road damage does not occur. Time restrictions may be imposed if rutting occurs in the woods or if excessive damage to the residual trees occurs. Dry or frozen ground conditions will be required for harvesting and hauling activities. Contractors must finish a listed block before moving into another block (A,B,C,D,E).
- New logging roads can only be built with prior approval of the County. Existing roads may be opened and improved and landing sites may be constructed with prior approval of the County. The sale is bisected by Trout Creek road. The main access to the west on Trout Creek road is a snowmobile trail. The main access to the eastern block is from a mountain bike/ski trail. Gates must be closed when no one is on site.
- Decking along Trout Creek road will only be allowed with the permission of Town of Woodboro. Any damage to the town road must be repaired by the contractors to the Town's requirements. Wood decking off the road must be kept far enough off the road so as not to pose a danger to traffic. Decking is permitted along the ski trails. Skidding on the ski trails is to be minimized to the extent possible. Landings and turn-arounds must have approval of the County prior to construction. The ski/bike trails must be returned to their original condition or better at the end of each harvest season. Skidding on or across the single track bike trail must be kept to a minimum. No ruts or tire impressions shall be left on the trails. All limbs 1/2 dia or larger must be removed from the trails. Top soil removed from trails must be spread back over trails to bring them to their original condition. Bond money will not be returned until all road/landing work is completed.
- Extreme care must be taken to protect the ski and bike trails. The single track bike trails must be kept completely clear of all debris (ALL slash) at the end of each day and at the end of the sale. The trails within and adjacent to the sale boundary will be closed down by the Ski/Bike Club during harvesting operations. A minimum of 3 days notice prior to starting operations must be given to the County by the Contractor to facilitate closing of the trails. RASTA shall install ski/bike trail closure signs on the trails.
- No equipment or slash is allowed in the wetland areas within or adjacent to the sale. Equipment may not be operated within 15 feet of any wetland unless ground is dry or frozen.
- Stay out of Retention Areas. Harvest all Red Paint lines and purple paint lines made by OCFD. Do not harvest trees with any small red rectangles, that are 1" by 4", which mark the bike trails.
- Slash must be pulled back a minimum of 25 ft from the edge of the mountain bike/ski trail and the town road and must be cut to no higher than 2 ft off the ground within 50 ft of the trail. Logging signs will be required on the town road while the sale is active.

Oneida County Forest Wash Trout Virus

Tract # 22 -20
Town of Woodboro
Contract No.: _____
Contractor: _____
Date Sold: _____
Date Completed: _____
Contract Length: 3 years

Compartment 30 / Stands 1 & 26
Harvest Area 35 Ac + 6 Ac Reserve = 41 Total Acres
Legal Desc. T36N R7E Sec. 2 SWSE, SESW, NESW,
Sec. 11 S1/2NE1/4, N1/2SE1/4, NENW



4" TOP	EST. VOLUME	MIN. BID
Aspen	1515 Tons (675 cd)	\$8.00/Ton
*Mx Hwd	475 Tons (200 cd)	\$7.70/Ton
WHOLE TREE	EST. VOLUME	MIN. BID
Aspen	2185 Tons (970 cd)	\$5.55/Ton
*Mx Hwd	775 Tons (325 cd)	\$4.72/Ton
EST. LOG VOLUME	MIN. BID	
OR	13 MBF	\$140.00/MBF

*Mx Hwd pulp includes: 71% red maple, 12% white birch, 16% red oak & 1% misc hardwoods.

Legend	
	Harvest Area
	Retention Area
G	Gate
B	Berm or Boulders
LM	Lake Minor
	Single Track Trail
	Ski Trail
BPL	Blue Paint Line
RPL	Red Paint Line
	Snowmobile Trail
	Section Corner
	Logging Road
	Town Road

Additional Regulations:


- In the Harvest Areas cut all aspen, maples, white birch, white ash, basswood, ironwood, and cherry 1" diameter and larger. Harvest all orange marked oak. Do not cut any other species, including Balsam fir. A MINIMUM OF 3 DAYS NOTICE PRIOR TO STARTING OPERATIONS MUST BE GIVEN TO THE COUNTY BY THE CONTRACTOR TO FACILITATE CLOSING THE TRAILS IN THE SOUTH UNIT. RASTA shall install ski/bike trail closure signs.
- Utilization on all species is a 100" stick to a 4" top or whole tree. If harvesting whole tree, every 10th tree top above the 4" diameter must be left evenly scattered in the harvest area. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard.
- Due to oak wilt and ski trail concerns, harvesting, skidding & hauling operations will only be permitted from July 15 through November 15 and as long as rutting and road damage does not occur. Time restrictions may be imposed if rutting occurs in the woods or on the roads or if excessive damage to the residual trees occurs.
- No new roads are to be built unless authorized by County. Existing roads may be opened and improved and landing sites may be constructed with prior approval of the County. The access roads must be blocked off with berms/boulders at the end of each harvest season and at the end of the sale. Gates must be closed when no one is on site. Bond money will not be returned until all road/landing rehabilitation is complete. Contractor shall install proper logging signs on roads for vehicular traffic.
- Decking is permitted along the all recreational trails. Skidding on the ski trails is to be minimized to the extent possible. Landings and turn-arounds must have approval of the County prior to construction. The ski/bike trails must be returned to their original condition or better at the end of each harvest season. Skidding on or across the single track bike trail must be kept to a minimum. No ruts or tire impressions shall be left on the trails. All limbs 1/2 dia or larger must be removed from the trails. Bond money will not be returned until all road/landing work is completed.
- Extreme care must be taken to protect the ski and bike trails. The single track bike trails must be kept completely clear of all debris (ALL slash) at the end of each day and at the end of the sale. The trails within and adjacent to the sale boundary will be closed down by the Ski/Bike Club during harvesting operations.
- Contractor shall acquire permission from the Town for decking on any Town Road. If wood is decked near the road, then it must be kept far enough off the road so as not to pose a danger to traffic. Any damage to Town roads must be repaired by the Contractor to Town requirements.
- No equipment or slash is allowed in the wetland areas within or adjacent to the sale. Equipment may not be operated within 15 feet of any wetland.
- All slash within 50 feet of any Town Road must be lopped and scattered not to be greater than 2' from the ground. Slash must be pulled back 25' from the edge of the Town Road and 10' from any recreational trails.
- Stay out of Retention Areas. Harvest all Red Paint lines made by OCFD. Do not harvest trees with any small red rectangles, that are 1" by 4", which mark the bike trails.
- All items listed in the Oneida County Timber Sale Contract apply. All applicable BMP's will be followed.

Compartment/Stand 72/22
 Harvest Area 15 Acres
 Legal Desc. T36N R4E Sec. 11 NESE,
 Sec. 12 NWSW

Oneida County Forest

Work Camp Hardwood Re-Sale

Tract 23-20
 Town of Lynne
 Contract No.: _____
 Contractor: _____
 Date Sold: _____
 Date Completed: _____
 Contract Length: 2 years



**NOTE: Sale was previously partially harvested.
 A new red paint line was established
 around the uncut area.**

4" Top	Est. Volume	Min. Bid
*Mx Hwd	115 Tons (45 cd)	\$7.60/Ton
Basswood	45 Tons (25 cd)	\$3.20/Ton
Logs		
Basswood	17 MBF	\$95.00/MBF
H. Maple	3 MBF	\$158.00/MBF
**Mx Hwd	2 MBF	\$95.00/MBF

* MX includes 89% H. maple, 11% red maple.
 **MX includes 56% ash and 44% red maple logs.


Legend		
	Previously Harvested	
	Marked Hardwood - Uncut	
		RPL Red Paint Line

Additional Regulations

1. In the uncut marked hardwood area cut all merchantable aspen, all trees marked with orange paint and all ironwood and balsam fir one inch diameter and larger. Within purple marked gaps cut all trees one inch diameter and larger, except oak saplings, including all purple marked trees leaving paint visible on the stump. Utilization on all species is a 100" stick to a 4" top. Any den or nest trees shall be left alone. Standing dead trees are not to be cut unless they pose a safety hazard to harvesting operations.
2. This sale can only be harvested when the ground is sufficiently dry or frozen to prevent rutting. Harvesting may only occur from July 15, to March 15 (spring break up). Additional time restrictions will be imposed if excessive rutting occurs in the woods or on the roads or if excessive damage to the residual trees occurs. If, in the opinion of the County, excessive damage to the residual stand cannot be avoided by the Contractor, additional harvesting restrictions will be imposed or the Contract may be cancelled.
3. Existing woods roads may be reopened. No new roads will be permitted. Following completion of the sale, all roads will be returned to their original condition or better. All roads that are currently bermed off or constructed shall be bermed or blocked with boulders at the completion of each harvest season and at completion of the sale. Bond money will not be returned until all road work is completed.
4. No equipment is allowed in the ephemeral ponds or wetlands within or adjacent to the sale unless the ground is frozen. All slash must be removed from ephemeral ponds and wetlands.
5. Stump height may not exceed 10". No skidding or decking on Work Road or in its ditches without the Town's permission.
6. The contractor shall comply with BMPs for invasive species and water quality.
7. All items listed in the Oneida County Timber Sale Contract apply.

Oneida County Forest

2-Piece Aspen



Approximate Sale Location

Tract # 25-20

Town of Lynne

Contract No.: _____

Contractor: _____

Date Sold: _____

Date Completed: _____

Contract Length: 4 years


Compartment / Stand 105/12

Harvest Area: 36 Ac total area, 34 cut acres, 2 acres retention/GTR

Legal Desc. T37N R4E

Sec. 21 S1/2 NE1/4, N 1/2 SE1/4, SE1/4 SE 1/4

Sec. 22 SW1/4 NW1/4, NW1/4 SW1/4



4" Top	Est. Volume	Min. Bid
Aspen	575 Tons (255 cd)	\$8.40/Ton
White Spruce	205 Tons (100 cd)	\$8.40/Ton
*MX Hardwood	1375 Tons (585 cd)	\$8.40/Ton
Balsam	145 Tons (70 cd)	\$4.90/Ton

Whole Tree	Est. Volume	Min. Bid
Aspen	795 Tons (355 cd)	\$6.08/Ton
White Spruce	290 Tons (145 cd)	\$5.94/Ton
*MX Hardwood	1945 Tons (835 cd)	\$5.94/Ton
Balsam	305 Tons (145 cd)	\$2.33/Ton

*MX Hardwood Pulp contains approximately 65% Red Maple, 21% White Birch, 13% Sugar Maple

Legend

	Clearcut Area	RPL	Red Paint Line
	Retention Area	+	Survey Corner
	Town Road	- - - -	Logging Road
	Snowmobile Trail		

Additional Regulations:

- In the Harvest Area cut all aspen, red maple, white birch, sugar maple, balsam fir and only cut white spruce greater than 8" and less than 18". Do not cut any red pine, black spruce, cedar, tamarack, cherry, white pine or red oak in the sale boundary. Utilization on all species is a 100" stick to a 4" top or whole tree. If harvesting whole tree, every 10th tree top above the 4" diameter must be left evenly scattered in the harvest area. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard. No trees are to be cut across the sale boundary and any trees that are felled across the sale boundary must be pulled back into the sale.
- Frozen ground conditions will be required for harvesting and hauling activities. Time restrictions may be imposed if excessive rutting occurs in the woods or on the roads or if excessive damage to the residual trees occurs.
- Existing roads may be opened and improved. Landing sites and additional roads may be constructed with prior approval of the County. The main access road is an old logging road. The road must either be rocked or bermed when no one is on site. All roads will be returned to their original condition or better at the end of the sale. Bond money will not be returned until all road/landing rehabilitation is complete.
- Decking on Willow road will only be allowed with the permission of Town of Lynne. Any damage will be immediately repaired to the satisfaction of the town. Wood decking off the road must be kept far enough off the road so as not to pose a danger to traffic.
- No equipment or slash is allowed in the wetland areas within or adjacent to the sale. Equipment may not be operated within 15 feet of any wetland unless ground is dry or frozen.
- Slash must be pulled back a minimum of 25 ft from the edge of the town road and cut to less than 2' high within 50' of the road. Logging signs will be required on the town road while the sale is active.
- All items listed in the Oneida County Timber Sale Contract apply. All applicable BMP's will be followed. Sale Est. BB/PF 7/20


Oneida County Forest

Rabid Rabbit

Compartment / Stand: 87/5, 90/6, 90/13, 96/1
 Harvest Area: 130 Ac: 123 ac cut, 7 ac reserve
 Legal Desc. T36N R4E
 Sec. 06 NE 1/4, NESE
 Sec. 07 SENE, E1/2 SE
 Sec. 08 SWNW, NWSW, SWSW, SESW
 Sec. 17 NWNW, NENW



Tract # 26-20
 Town of Lynne
 Contract No.: _____
 Contractor: _____
 Date Sold: _____
 Date Completed: _____
 Contract Length: 4 years




4" Top	Est. Volume	Min. Bid
Aspen	4300 Tons (1900 cd)	\$8.40/Ton
*MX Hardwood	2450 Tons (1065 cd)	\$8.40/Ton
Balsam	120 Tons (55 cd)	\$4.90/Ton
Sawlogs		
**MX Hardwood	63 MBF	\$95.00/MBF
Hard Maple	10 MBF	\$158.00/MBF
Whole Tree		
Aspen	5930 Tons (2635 cd)	\$6.09/Ton
*MX Hardwood	3750 Tons (1630 cd)	\$5.49/Ton
Balsam	210 Tons (100 cd)	\$2.80/Ton
Sawlogs		
**MX Hardwood	63 MBF	\$95.00/MBF
Hard Maple	10 MBF	\$158.00/MBF
*MX Hardwood Pulp contains approximately 75% R Maple, 12% Hard Maple, 9% White Birch, 3% Ash, 1% Basswood		
**MX Logs: 91% Red Maple, 4% White Birch, 4%		

Legend	
	Aspen
	Hardwood
	Retention Area
	Town Road
	Red Paint Line
	Yellow Paint Line
	Survey Corner
	Marsh

- Additional Regulations:**
- In the Harvest Area A (Aspen) cut all trees EXCEPT for Spruce smaller than 8" or larger than 18". In Harvest Area B (Hardwood) cut all trees EXCEPT for those marked in GREEN, White Birch less than 6", and Spruce smaller than 8" or larger than 18". No whole tree skidding allowed in Area B to protect hardwood regeneration. Damage to hardwood regeneration must be kept to a minimum. Utilization on all species is a 100" stick to a 4" top or whole tree. If harvesting whole tree, every 10th tree top above the 4" diameter must be left evenly scattered in the harvest area. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard.
 - Frozen ground conditions will be required for harvesting and hauling activities. Access trails have numerous wet areas and the presence of numerous tag alder draws within the sale will require frozen ground. Time restrictions may be imposed if excessive rutting occurs in the woods or on the roads or if excessive damage to the residual trees occurs.
 - No new roads will be permitted. Existing roads may be opened and improved and landing sites may be constructed with prior approval of the County. Roads must be leveled and blocked with a berm or rocks at the end of each harvest season and upon completion of the sale. Performance bond money will not be returned / released until all road/landing rehabilitation is complete.
 - Decking on South Turcott Road will only be allowed with the permission of the Town of Lynne. Any damage to the road will be immediately repaired to the satisfaction of the Town.
 - No equipment or slash is allowed in the wetland areas within or adjacent to the sale. Equipment may not be operated within 15 feet of any wetland unless ground is dry or frozen.
 - Slash must be pulled back a minimum of 10 ft from the edge of the town road and must be cut to no higher than 2 ft off the ground within 50 ft of the road.
 - All items listed in the Oneida County Timber Sale Contract apply. All applicable BMP's will be followed.


Oneida County Forest Willow West Ash

Compartment / Stand 103/7 & 8
Harvest Area: 103 Ac + 6 Ac Reserve
Legal Desc. T37N R4E Sec. 16 SESW, SWSE,
Sec. 21 E1/2SW, E1/2NW, NWNE



Tract # 21-17
Town of Lynne
Contract No.: _____
Contractor: _____
Date Sold: _____
Date Completed: _____

Contract Length: 4 Years



4" Top	Est. Volume	Min. Bid
Aspen	45 Tons (20 cd)	\$5.50/Ton
MX Hardwood (MX Hardwood contains approximately 73% BI Ash, 17% Red Maple, 8% W Birch and 2% H Maple)	2585 Tons (1055 cd)	\$5.50/Ton
Balsam Fir	310 Tons (145 Cd)	\$2.30/Ton
Tamarack/BI Spruce (95% Tamarack, 5% BI Spr)	105 Tons (46 Cd)	\$5.50/Ton
Sawlogs	Est. Volume	Min. Bid
Black Ash	45 MBF	\$119.00/MBF
R Maple	5 MBF	\$119.00/MBF

Legend	
	Black Ash Area: 60 Ac
	Cedar Area: 36 Ac
	Hardwood Area: 4 Ac
	Tamarack Area: 3 Ac
	Reserve Areas: 6 Ac
	RPL Red Paint Line
	Survey Corner
	GPS Control Monument
	Logging Road
	Town Road

Harvest Regulations

- In the **Black Ash (60 Ac) and Cedar Areas (36 Ac)**, harvest only those Black Ash LARGER than 8" diameter breast height (DBH), and all Balsam Fir, Red Maple and White Birch 1" dbh and larger.
In the **Hardwood Area (4 Ac)** Harvest all maple, white birch, aspen and balsam fir except those marked with green paint.
In the **Tamarack Area (3 Ac)** Harvest all Tamarack and Black spruce except those marked with green.
Utilization on all species is a 100" stick to a 4" top. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard.
NO WHOLE TREE UTILIZATION.

No equipment or harvesting is allowed in the green lined areas within the black ash area. Intermittent streams are located in these areas. No slash is to be left within these areas.

- Frozen ground conditions will be required for harvesting and hauling activities. This site is wet and will require preparation to freeze down travel lanes prior to commencing harvesting or skidding.
- No decking or skidding is permitted on Willow Rd or West Rd or within their ditches without permission from the Town of Lynne. All landings and roads must have approval of the County prior to construction. Following completion of the sale, all trails and landings will be returned to their original condition or better. All new access roads will be bermed off or blocked with boulders at the completion of each harvest season and at completion of the sale. Bond money will not be returned until all road work is completed.
- Slash must be pulled back a minimum of 25' from West Road and shall be cut to within 2' of the ground in this area. No other slash treatment is needed outside the 25' road zone.
- Stump height shall not exceed 10" within the entire sale area.
- All items listed in the Oneida County Timber Sale Contract apply. All applicable BMP's will be followed.

Oneida County Forest

East Side Ash

Compartment / Stand 105/2

Harvest Area: 78 Acres

Legal Desc. T37N R4E Sec 15: S1/2SW,
Sec. 16 SESE, Sec. 21 NENE, Sec 22: N1/2NW

★ Approximate Sale Location

Tract # 20-18

Town of Lynne


Contract No.: _____

Contractor: _____

Date Sold: _____

Date Completed: _____

Contract Length: 4 years



4" Top	Est Vol	Min Bid
Black Ash*	1900 T (932 cd)	\$7.50/T
* 90% BI Ash, 10% W Birch		
Logs		
Black Ash**	31 mbf	\$128.00/mbf
** 90% BI Ash, 10% W Birch		

Legend

	Sale Area		Red Paint Line
	Logging Road		Survey Corner
	Snowmobile Trail		Hemlock Pocket
	Power Line		Berm
	Intermittent Stream		Gate

Harvest Regulations

1. In the sale area, harvest only those Black Ash LARGER than 8" diameter breast height (DBH), and White Birch containing one or more merchantable sticks (100" stick to a 4" top). Do not cut any other species. Utilization on all species is a 100" stick to a 4" top. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard.
NO WHOLE TREE UTILIZATION.

2. Frozen ground conditions will be required for harvesting and hauling activities. This site is wet and will require preparation to freeze down travel lanes prior to commencing harvesting or skidding. Tops should be used as mats to operate equipment if ground is not completely frozen. Rutting will not be tolerated.

3. All landings and roads must have approval of the County prior to construction. Following completion of the sale, all trails and landings will be returned to their original condition or better. All access roads will be bermed off or blocked with boulders at the completion of each harvest season and at completion of the sale. Bond money will not be returned until all road work is completed.

4. If the snowmobile trail east of the sale area is used for access, the trail must be kept open and in a safe, useable condition at all times during snowmobile season. Any wood decked on the trail must be far enough off the trail so as not to pose a safety hazard. Cautionary signs shall be placed on the snowmobile trail whenever it is being used for logging purposes.

5. There is an intermittent drainage (marked in green paint) running through the sale. No skidding across this drainage unless it is completely frozen. No slash is to be left in the drainage channel. Do not harvest trees within 35 feet of the green lined drainage.

6. Stump height shall not exceed 10" within the entire sale area.


7. All applicable BMP's will be followed on all aspects of the sale.

8. All items listed in the Oneida County Timber Sale Contract apply.


Sale Est. J Leith, WOD DNR 2/18.

Oneida County Forest Shingle Mill Ash

Compartment / Stand 12/9
Harvest Area: 49 Acres
Legal Desc. T35N R9E Sec 21: NWSW,
Sec. 22 E1/2SE, NWSE, SWNE, SENW



Tract # 21-18
Town of Enterprise
Contract No.: _____
Contractor: _____
Date Sold: _____
Date Completed: _____
Contract Length: 4 years



4" Top	Est. Volume	Min. Bid
Mx Hwd*	1225 T (500 cd)	\$8.20/T
Balsam Fir	355 T (167 cd)	\$6.30/T
Aspen	275 T (122 cd)	\$8.20/T
*45% W Birch, 29% BI Ash, 26% R Maple		

Logs		
Mx Hwd**	8 mbf	\$103.00/mbf
** 75% BI Ash, 15% W Birch, 10% R Maple,		

Legend			
	Sale Area		County Forest Road
	Reserve Area		Red Paint Line
	Logging Road		Blue Paint Line
	Snowmobile/ATV Route		Survey Corner


Harvest Regulations

- In the sale area, harvest only those Black Ash 8" diameter breast height (DBH) and larger, and all merchantable Aspen, Balsam Fir, Red Maple and White Birch. Do not cut any other species. Utilization on all species is a 100" stick to a 4" top. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard.
NO WHOLE TREE UTILIZATION.
- Frozen ground conditions will be required for harvesting and skidding activities. This site is wet and may require preparation to freeze down travel lanes prior to commencing harvesting or skidding. Tree tops shall be used for travel mats when needed. Rutting will not be tolerated.
- An access road from Shingle Mill Rd to the sale area will be required. The location of this access along with landing sites must have approval of the County prior to construction. All access roads will be bermed off or blocked with boulders at the completion of each harvest season and at completion of the sale. Bond money will not be returned until all road work is completed.
- Wood may be decked along the north side of Shingle Mill Road only. Skidding may only occur when road is dry or frozen. Any damage to the road will be repaired by the contractor. This includes grading, ditching and graveling if needed. The road must be kept in a safe, useable condition at all times. Wood decks must be far enough off the road so as not to pose a safety hazard. Cautionary signs shall be placed on Shingle Mill Road by the contractor whenever sale is active.
- Absolutely no activity is to occur in the Reserve Area south of Shingle Mill Rd. to protect an old logging camp site. Any trees felled across the blue lines must be pulled back onto county property before limbing. No tops from trees harvested in upland areas are to be left in any lowland area.
- All applicable BMP's will be followed on all aspects of the sale.
- All items listed in the Oneida County Timber Sale Contract apply. Sale Est. PF 4/18.

Oneida County Forest

Lame Musky Sale

Compartment / Stand 82/8, 18, 24 and 105/1, 18
 Harvest Area: 162 Acres Harvest 34 Ac Reserve
 Legal Desc. T37N R4E
 Sec 21: S1/2NE, NWSE, SESE
 Sec 22, W1/2SW, Sec 28 N1/2NE,
 Sec 34 E1/2SW, E1/2NW, W1/2NE, W1/2SE
 T36N R4E: Sec 3 N1/2NW



Tract # 10-19
 Town of Lynne
 Contract No.: _____
 Contractor: _____
 Date Sold: _____
 Date Completed: _____
 Contract Length: 4 years

Legend

	Sale Area		Red Paint Line
	Logging Road		Green Paint Line
	Snowmobile Trail		Survey Corner
	Power Line		Berm
	Intermittent Stream		Gate



4" Top	Est Vol	Min Bid
Mx Hwd*	4445 T (1815 cd)	\$5.60/T
Tamarack	430 T (185 cd)	\$2.40/T
Balsam	325 T (153 cd)	\$4.20/T
Spruce**	205 T (103 cd)	\$7.10/T
Aspen	185 T (82 cd)	\$5.60/T

*Mx = 72% Bl Ash, 19% R Maple, 9% W Birch
 ** Spruce = 83% Bl Spruce 17% W Spruce

Logs		
Mx Hwd**	80 mbf	\$105.00/mbf

** 88% Bl Ash, 10% R Maple 2% W Birch


SEE REGULATIONS
 PAGE 2



Oneida County Forest

Lame Musky Sale

Compartment / Stand 82/8, 18, 24 and 105/1, 18
 Harvest Area: 162 Acres Harvest 34 Ac Reserve
 Legal Desc. T37N R4E
 Sec 21: S1/2NE, NWSE, SESE
 Sec 22, W1/2SW, Sec 28 N1/2NE,
 Sec 34 E1/2SW, E1/2NW, W1/2NE, W1/2SE
 T36N R4E: Sec 3 N1/2NW



Tract # 10-19
 Town of Lynne
 Contract No.: _____
 Contractor: _____
 Date Sold: _____
 Date Completed: _____
 Contract Length: 4 years

Legend	
	Sale Area
	Logging Road
	Snowmobile Trail
	Power Line
	Intermittent Stream
	Red Paint Line
	Green Paint Line
	Survey Corner
	Berm
	Gate

4" Top	Est Vol	Min Bid
Mx Hwd*	4445 T (1815 cd)	\$5.60/T
Tamarack	430 T (185 cd)	\$2.40/T
Balsam	325 T (153 cd)	\$4.20/T
Spruce**	205 T (103 cd)	\$7.10/T
Aspen	185 T (82 cd)	\$5.60/T

*Mx = 72% BI Ash, 19% R Maple, 9% W Birch
 ** Spruce = 83% BI Spruce 17% W Spruce

Logs		
Mx Hwd**	80 mbf	\$105.00/mbf

** 88% BI Ash, 10% R Maple 2% W Birch

SEE MAP
PAGE 1

Harvest Regulations

- In the sale area, harvest all Aspen, only those Black Ash, Red Maple and Tamarack LARGER than 8" diameter breast height (DBH), White Birch and Balsam Fir containing one or more merchantable sticks (100" stick to a 4" top) and All Black and White Spruce between 8" dbh and 18" dbh. Do not cut any other species. Utilization on all species is a 100" stick to a 4" top. Any den or nest trees shall be left uncut. Standing dead trees are not to be cut unless they pose a safety hazard. NO WHOLE TREE UTILIZATION. Due to the need to run machinery on tree top mats, NO HOTSAW/FELLER BUNCHER operations will be permitted.
- Frozen ground conditions will be required for harvesting and hauling activities. This site is wet and will require preparation to freeze down travel lanes prior to commencing harvesting or skidding. Tops should be used as mats to operate equipment if ground is not completely frozen. Rutting will not be tolerated.
- All landings and roads must have approval of the County prior to construction. Following completion of the sale, all trails and landings will be returned to their original condition or better. All access roads will be bermed off or blocked with boulders at the completion of each harvest season and at completion of the sale. Bond money will not be returned until all road work is completed.
- If the snowmobile/ATV trail east of the sale area is used for access, the trail must be kept open and in a safe, useable condition at all times during snowmobile season. Any wood decked on the trail must be far enough off the trail so as not to pose a safety hazard. Cautionary signs shall be placed on the snowmobile trail whenever it is being used for logging purposes.
- There is an intermittent drainage (marked in green paint) running through the sale. No skidding across this drainage unless it is completely frozen. No slash is to be left in the drainage channel. Do not harvest trees within the green lined drainage.
- Stump height shall not exceed 10" within the entire sale area.
- All applicable BMP's will be followed on all aspects of the sale.
- The grass opening along Willow Rd north of West Rd is the site of an old logging camp and may not be used for any logging activities.
- All items listed in the Oneida County Timber Sale Contract apply. Sale Est. P Fiene, E Rady, J Renik, 3/19.

Compartment/Stand: 88/3, 88/4

ONEIDA COUNTY FOREST

Tract #12-19

Town of Lynne

Harvest Area: 125 acres (includes 5 Ac Reserve) 7 Island Hardwood

Contract No. _____

Legal Desc; T36N R4E Sec. 8 E1/2NE, SE1/4;
Sec. 9 W1/2NW, NWSW; Sec. 16 W1/2NW
Sec. 17: N1/2NE


Contractor _____

Date Sold _____

4 Year Contract

Date Completed _____

Legend	
	Hardwood Thinning 94 Ac
	Regen Areas 26 Ac Cut
	Reserve Area 5 Ac
	Town Rd
	Logging Road
	RPL Red Paint Line
	+ Survey Corners
	— Snowmobile Trail
	G Grass Opening
	⌋ Keg/Wetland



4" Top		
Est. Volume		Min. Bid
Mx Hwd	2100 T (857 cd)	\$6.20/Ton
40% R Maple, 35% H. Maple, 25% W Birch		
Aspen	895 T (398 cd)	\$6.30/Ton
Basswood	145 T (76 cd)	\$2.60/Ton
Logs		
Mx Hwd	60 mbf	\$100.00/mbf
45% R Maple, 28% W Birch, 16% H Maple, 11% Misc.		
Basswood	38 mbf	\$90.00/mbf

Whole Tree		
Est. Volume		Min. Bid
Mx Hwd	2995 T (1222 cd)	\$4.35/Ton
40% R Maple, 35% H. Maple, 25% W Birch		
Aspen	1150 T (511 cd)	\$4.90/Ton
Basswood	175 T (91 cd)	\$2.15/Ton
Logs		
Mx Hwd	60 mbf	\$100.00/mbf
45% R Maple, 28% W Birch, 16% H Maple, 11% Misc.		
Basswood	38 mbf	\$90.00/mbf

Access Coords
45.6010
-89.98203

Scale: 1" = 1/4 mi.

ONEIDA COUNTY FOREST

7 Island Hardwood

Compartment/Stand: 88/3, 88/4

Harvest Area: 125 acres (Includes 5 Ac Reserve)

Legal Desc; T36N R4E Sec. 8 E1/2NE, SE1/4; Sec. 9 W1/2NW, NWSW; Sec. 16 W1/2NW
Sec 17: N1/2NE

Tract #12-19

Town of Lynne

Contract No. _____

Contractor: _____

Date Sold: _____

Date Completed: _____

Contract Length: 4 Years

4" Top

Est. Volume	Min. Bid
Mx Hwd 2100 T (857 cd) 40% R Maple, 35% H. Maple, 25% W Birch	\$6.20/Ton

Aspen 895 T (398 cd)	\$6.30/Ton
----------------------	------------

Basswood 145 T (76 cd)	\$2.60/Ton
------------------------	------------

Logs

Mx Hwd 60 mbf 45% R Maple, 28% W Birch, 16% H Maple, 11% Misc.	\$100.00/mbf
----------------------------------------------------------------------	--------------

Basswood 38 mbf	\$90.00/mbf
-----------------	-------------

Whole Tree

Est. Volume	Min. Bid
Mx Hwd 2995 T (1222 cd) 40% R Maple, 35% H. Maple, 25% W Birch	\$4.35/Ton

Aspen 1150 T (511 cd)	\$4.90/Ton
-----------------------	------------

Basswood 175 T (91 cd)	\$2.15/Ton
------------------------	------------

Logs

Mx Hwd 60 mbf 45% R Maple, 28% W Birch, 16% H Maple, 11% Misc.	\$100.00/mbf
----------------------------------------------------------------------	--------------

Basswood 38 mbf	\$90.00/mbf
-----------------	-------------

Legend

-  Hardwood Thinning
94 Ac
-  Regen Areas
26 Ac
-  Reserve Areas 5 Ac
-  Town Road
-  Logging Road
-  Snowmobile Trail
-  G Grass Opening
-  Keg/Wetland
-  RPL Red Paint Line
-  + Survey Corners

SEE MAP PAGE 2

Additional Regulations

1. In the Marked Hardwood areas harvest all Aspen, W. Birch, Ironwood, and only those hardwood marked with orange paint. Within the purple painted gaps harvest all trees 1" dia. or larger (except Oak) and all purple marked trees. In the area marked A on the map harvest all Aspen, Ironwood and Balsam Fir and only those hardwood containing one or more sticks to a 4" top. In all other Regeneration Areas harvest all trees except Pine, Spruce, Black Ash and those W Birch marked with green paint. Utilization is 100" stick to a 4" top or whole tree in all areas.
2. If harvesting whole tree, 1 in 10 tops above the standard 4" dia. must be left in the woods and evenly scattered throughout the sale.
3. Do not cut any standing dead trees unless they pose a safety hazard. Tops may be left intact to protect regeneration from deer browse.
4. DO NOT damage the residual hardwood or hardwood regeneration. If in the opinion of the county, excessive damage is being done to the residual trees or hardwood regeneration additional regulations (such as fixed head harvester only or no hot saws) may be imposed or the contract may be cancelled.
5. Due to wetland access to the sale, frozen ground conditions will be required in all areas. **Work to freeze down access roads will need to be done prior to moving in to begin harvesting.**
6. A red paint line was placed across the tamarack/tag alder showing the shortest access to the northeast island. (dotted line on map)
7. Construction of new roads and landings must be approved by the county forester prior to construction. All roads and landings must be leveled at the end of each harvest season and at the end of the sale. Bond money will not be returned until all road/landing work is completed.
8. No equipment is permitted in the lowland areas within or adjacent to the sale unless ground is frozen. Stump height may not exceed 10". No equipment allowed in Reserve Areas except on existing roads.
9. BMP's must be followed on all aspects of the sale.
10. All terms of the Timber Sale Contract also apply.